BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/20/2020-21 Date: 29.03.2021

Indent No: BBMP/2020-21/WS/WORK_INDENT42861/CALL-2

SCHEDULE -B

Name of Work: Providing drinking water supply in Ward No 17

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	380.88	Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications.	Cum	499.00	Rupees Four Hundred Ninety Nine Only
2	1058.00	Providing and fixing to wall, ceiling and floor, medium density polyethylene pipes 6.00 kgs/sq.cm working pressure of outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor including cost of all materials, labour charges, HOM and testing complete as per specifications. Specification No.KBS 13.2.15.1 / 13.9 for internal water supply connection KSRB13-8.6 : -do- 63mm	Mtrs	329.00	Rupees Three Hundred Twenty Nine Only
3	1658.00	Providing and fixing chorinated poly vinyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall) 20mm nominal OD pipes	Mtrs	173.00	Rupees One Hundred Seventy Three Only
4	380.88	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications	Cum	135.00	Rupees One Hundred Thirty Five Only
5	20.00	C.I wheel of approved quality (screwed end) nominal bore including cost of all materials, labour and HOM with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3 KSRB13-6.3-6 - do - 50 mm dia nominal	Each	1934.00	Rupees One Thousand Nine Hundred Thirty Four Only
6	120.00	Making connection of G.I distribution branch with G.I main of 25 to 40mm nominal bore, including cutting and threading the pipes, providing and fixing Tee, nuts, labour for all item of works, testing and HOM complete as per specifications.	Nos	537.00	Rupees Five Hundred Thirty Seven Only
7	100.00	Providing and fixing in position brass stop cock of approved quality nominal bore including cost of all materials, labour and HOM with all leads complete as per specifications.	Each	157.00	Rupees One Hundred Fifty Seven Only

Kumar. C

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

8	79.35	Providing and laying in position plain cement concrete of Mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications. Specification	Cum	5673.00	Rupees Five Thousand Six Hundred Seventy Three Only
9	52.90	Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	6070.00	Rupees Six Thousand Seventy Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP